


Big Magnet Design II:

- a) solenoid and cable concept
- b) short section test



V.V. Kashikhin and A.V. Zlobin

Magnetic cavern design II

Fields





1 m iron wall thickness.
~2.4 T peak field in the iron.
Good field uniformity



Fr and Fz

Fr (middle/end turns)

Fz (end turns)




The largest force component => drives the mechanical design.


Parameters

PARAMETER	UNIT	DESIGN With iron
I_{solenoid}	MA	7.5
$N_{\text{turns/solenoid}}$		150
I_{turn}	kA	50
$ B _{\text{average in XZ}}$	T	0.579
W_{total}	GJ	3.95
L_{total}	H	3.16
F_r maximum	kN/m	15.67
F_x maximum	kN/m	39.57


Original Solenoid and cable design



- Pipetron type cable
 - Needs modification to provide long length (~5-7 km) and flexibility (bending diameter 15 m)
- Solenoid strongback
- Assembly procedure



New support structure and cable



Structure:




- Cable vacuum shell is now part of the solenoid support structure
- LN shield is fabricated and installed independently:

- two half-shells with LN pipes
- super-insulation,
- supports

Cable installed inside the LN shield:

- thick He pipe with SC and Cu wires wound outside
- thick Al or Cu tape (mechanical support and additional stabilizer) wrapped over SC/Cu wires
- superinsulation
- flexible (± 2 mm dynamic range) supports

1-2 turn solenoid model



Goals:

- Develop and optimize cable design, thermal shield, support structure, superinsulation
- Fabricate and test ~50m long cable and LN shield
- Test solenoid support structure and assembly procedure (thermal shield and cable installation)
- Cable splicing (mechanical, electrical)
- Test cable support structure mechanics (longitudinal and transverse):
 - Fr(body)~6-10 kN/m
 - Fr(end)~15 kN/m
 - Fz(end)~29-29 Kn/m
- Measure static heat leaks at different currents to LN and LHe levels

<=Single turn

Pipetron Magnet Test facility

- PS~100kA
- Current leads 100 kA
- Cryogenic system
- Quench detection and protection systems
- DAQ

Next step:

- Check the availability of this equipment and space
- Experiment plan, schedule and cost estimate